


COMMERCIAL APRON AND SIDEWALK



NOTES:

1. ALL AGGREGATE SUB BASE SHALL BE MECHANICALLY COMPACTED
2. SIDEWALK SHALL CONTINUE THROUGH DRIVEWAYS
3. DRIVEWAYS & SIDEWALK THICKNESS ACROSS DRIVEWAYS SHALL BE A MINIMUM OF 8" PCC ON 4" AGGREGATE SUB BASE
4. DETECTABLE WARNINGS SHALL ONLY BE INSTALLED AT DRIVEWAYS WITH PERMANENT TRAFFIC CONTROL DEVICES.
5. SIDEWALK CONSTRUCTION SHALL FOLLOW APPLICABLE IDOT STANDARDS
6. SIDEWALKS SHALL FOLLOW CURRENT ADA GUIDELINES
7. REINFORCING WIRE AND/OR BARS ARE PROHIBITED IN SIDEWALK OR APRON

filename ac: Std Commercial Driveway

REVISIONS:

1. 2/14/2025

2. 1/13/2026



Hanover Park ^{USA}

COMMERCIAL APRON & SIDEWALK
STANDARD DETAIL